MogoCDANI		Construc	tion Live Loa	Shoring Tables						
MegaSPAN		20 Ga. Steel deck thickness Maximum unshored span length for shoring lines in feet (ft.)					Load Resistance Factor Design			
COMPOSITE FLOORING SYSTEM	Maximum						Imperial			
Number of shoring lines required		Total slab thickness (in.)								
Number of Shoring lines required	10.5"	11.0"	11.5"	12.0"	12.5"	13.0"	13.5"	14.0"		
None	15.78	15.24	14.74	14.30	13.89	13.51	13.17	12.82		
1 line at center of span	19.61	17.67	16.08	14.76	13.63	12.67	11.83	11.10		
2 lines equally spaced across span	33.43	30.12	27.42	25.15	23.24	21.59	20.16	18.91		


Maga CDANI		Construc	tion Live Loa	Shoring Tables						
MegaSPAN		18 Ga. Steel deck thickness Maximum unshored span length for shoring lines in feet (ft.)					Load Resistance Factor Design			
COMPOSITE FLOORING SYSTEM	Maximum						Imperial			
Number of shoring lines required										
Number of Shoring lines required	10.5"	11.0"	11.5"	12.0"	12.5"	13.0"	13.5"	14.0"		
None	16.55	16.13	15.76	15.43	15.12	14.85	14.51	14.16		
1 line at center of span	26.27	24.17	22.38	20.83	19.25	17.89	16.71	15.68		
2 lines equally spaced across span	36.08	36.08	36.08	35.50	32.81	30.50	28.49	26.73		

MagaSDANI		Construc	tion Live Loa	Shoring Tables						
MegaSPAN	16 Ga. Steel deck thickness					Load Resistance Factor Design				
COMPOSITE FLOORING SYSTEM	Maximum	Maximum unshored span length for shoring lines in feet (ft.)					Imperial			
Number of shoring lines required	Total slab thickness (in.)									
Number of shoring lines required	10.5"	11.0"	11.5"	12.0"	12.5"	13.0"	13.5"	14.0"		
None	17.62	17.17	16.78	16.43	16.11	15.82	15.56	15.31		
1 line at center of span	36.08	36.08	33.65	31.35	29.35	27.58	26.02	24.62		
2 lines equally spaced across span	36.08	36.08	36.08	36.08	36.08	36.08	36.08	36.08		

TABLE NOTES:

- 1. Purpose of this table is to provide guidance on the required number of shoring lines.
- 2. Maximum unshored span values in above tables are limited to the maximum spans based on strength and deflection criteria of L/180 or max.3/4 inch as per ANSI C-2017 and AISI S100-2016.
- 3. Max. Prop spacing and shoring configuration as per the specifications of used shoring system and to be confirmed by the Project's Shoring Engineer.
- 4. Values are based on Normal Denisty of Concrete = 145 pcf.
- 5.The uniform construction live load of 21 psf is considered adequate for typical construction applications that consists of transport and placement by hose and finishing by hand tools. If concrete is poured using bucket/chutes and heavier equipments are used for finishing, uniform construction live load of 50 psf or higher to be used.

TYPICAL SHORING SECTIONS:



MegaSPAN	Construction Live Load - 50 psf					Shoring Tables				
	20 Ga. Steel Deck Thickness					Load Res	or Design			
COMPOSITE FLOORING SYSTEM	Maximum	Maximum unshored span length for shoring lines in feet (ft.)					Imperial			
Number of shoring lines required	Total slab thickness (in.)									
Number of Shoring lines required	10.5"	11.0"	11.5"	12.0"	12.5"	13.0"	13.5"	14.0"		
None	13.04	12.72	12.43	12.16	11.91	11.67	11.44	11.23		
1 line at center of span	15.52	14.53	13.66	12.88	12.19	11.57	11.01	10.50		
2 lines equally spaced across span	26.46	24.77	23.28	21.96	20.78	19.72	18.77	17.90		

MogaSDANI	Construction Live Load - 50 psf					Shoring Tables				
MegaSPAN		18 Ga. Steel Deck Thickness Maximum unshored span length for shoring lines in feet (ft.)					Load Resistance Factor Design			
COMPOSITE FLOORING SYSTEM	Maximum						Imperial			
Number of shoring lines required	Total slab thickness (in.)									
Number of Shoring lines required	10.5"	11.0"	11.5"	12.0"	12.5"	13.0"	13.5"	14.0"		
None	14.37	14.03	13.71	13.41	13.13	12.87	12.62	12.39		
1 line at center of span	20.55	19.24	18.09	17.07	16.16	15.34	14.60	13.92		
2 lines equally spaced across span	35.03	32.80	30.84	29.10	27.54	26.14	24.88	23.74		

Maga CDANI		Construc	tion Live Loa	Shoring Tables						
MegaSPAN		16 Ga. Steel Deck Thickness					Load Resistance Factor Design			
COMPOSITE FLOORING SYSTEM	Maximum	Maximum unshored span length for shoring lines in feet (ft.)					Imperial			
Number of shoring lines required		Total slab thickness (in.)								
Number of Shoring lines required	10.5"	11.0"	11.5"	12.0"	12.5"	13.0"	13.5"	14.0"		
None	16.49	16.10	15.74	15.40	15.08	14.78	14.50	14.23		
1 line at center of span	30.93	28.98	27.25	25.72	24.36	23.13	22.02	21.01		
2 lines equally spaced across span	52.72	49.39	46.45	43.85	41.52	39.42	37.53	35.81		

TABLE NOTES:

- 1. Purpose of this table is to provide guidance on the required number of shoring lines.
- 2. Maximum unshored span values in above tables are limited to the maximum spans based on strength and deflection criteria of L/180 or max.3/4 inch as per ANSI C-2017 and AISI S100-2016.
- 3. Max. Prop spacing and shoring configuration as per the specifications of used shoring system and to be confirmed by the Project's Shoring Engineer.
- 4. Values are based on Normal Denisty of Concrete = 145 pcf.
- 5.The uniform construction live load of 21 psf is considered adequate for typical construction applications that consists of transport and placement by hose and finishing by hand tools. If concrete is poured using bucket/chutes and heavier equipments are used for finishing, uniform construction live load of 50 psf or higher to be used.

TYPICEL SHORING SECTIONS:

